

CW Treatment Plant

Design, Engineering, manufacture, inspection and testing at vendor's/ sub vendor's works, painting, forwarding, proper packing, shipment, delivery at site, unloading, handling & transportation at site, erection & commissioning, testing, trial operation, performance guarantee testing and handing over of CW treatment plant for a Power Project having dosing of scale inhibitor, corrosion inhibitor and sulphuric acid dosing system using dosing tanks and metering pumps. The plant shall be fully automatic/semiautomatic PLC/DCS based.